



Performances of the Elettra Booster and Storage Ring RF Systems

*Alessandro Fabris, Mauro Bocciai, Luca Bortolossi,
Marco Ottobretti, Cristina Pasotti, Mauro Rinaldi
Sincrotrone Trieste, Trieste, Italy.*

Overview /Booster/SR-60 kW/SR-150 kW/Conclusions

□3 types of 500 MHz RF systems in Elettra

□Booster:

□5-cells cavity, 60 kW (klystron).

□SR plants in sections 2,3,8:

□Elettra type cavity, 60 kW (klystron).

□SR plant in section 9:

□Elettra type cavity, 150 kW (2 x 80 kW IOTs).



Booster RF System Design Specifications		
	Nominal	Low emittance
Beam energy	2.5 GeV	2.5 GeV
Beam current	4 mA	4 mA
RF frequency	499.654 MHz	499.654 MHz
Rep. frequency	3 Hz	3 Hz
RF voltage	840 kV	730 kV
Cavity power	25.2 kW	19.1 kW
Beam power	1.9 kW	1.9 kW
Total power	27.1 kW	21.0 kW

□ **CAVITY**


- **5 cells cavity.**
- **Tested at 54 KW.**
- **Multipacting strong up to 8 kW.**
- **Implemented an automatic conditioning procedure via control system.**

□ **BOOSTER MILESTONES:**

□ **Installation from April 2007.**

□ **Commissioning from September 2007.**

□ **First injection for users: March 3rd, 2008 as planned.**



Overview / **Booster** / SR-60 kW / SR-150 kW / Conclusions



□ **POWER PLANT**

□ 60 kW 500 MHz.

□ Klystron based power amplifier (K3672BCD from E2V).

□ All components from SR upgrade.

□ **LLRF**

□ Three loops:

□ Frequency and field flatness.

□ Amplitude.

□ Phase.

□ Analog system.

□ System can work with almost any duty cycle up to cw and different waveforms.




□ RF VOLTAGE WAVEFORM

- Sinusoidal energy ramp (160 ms).
- Capture: 40 kV (33.7 kV theoretical).
- **Extraction 2 GeV: 300 kV (1 sec τ_q).**
- **A linear curve has been used (delayed with respect to the energy ramp).**

□ PERFORMANCES:


- 4000 hours of operation.
- System has been reliable and easy to use for the operators.
- Faults:
 - Spurious circulator arc trips during the first commissioning weeks, related to radiation (improved the shielding).
 - Random reflected power trips related to a malfunctioning of the trigger signal to the frequency loop (trigger provided by the control system).
- In view of top-up operation, the system has been kept in ramped operation on a 24 hours/day basis for two months: no problem encountered.



Overview /Booster/**SR-60 kW**/SR-150 kW/Conclusions

□60 kW PLANTS (SECTIONS 2,3,8):

- Original plants installed in 1993.
- Operating hours around 85000.
- Elettra type cavities.
- Klystron based amplifier (K3672BCD from E2V).



□PERFORMANCES (last two years)

□The system is very reliable.

□AMPLIFIERS

□The last klystron replacement was in **October 2004 (oldest klystron now nearly 60000 hours)**.

□Klystron emission quite stable. Periodically retuned.

□Body current trips on plant 3 and 8 caused by overdrive when beam was killed, solved by retuning the tube at the following shutdown.

□CIRCULATORS AND COAXIAL LINES

□Few circulator arc trips (two in the last 2 years).

□We tolerate them.

□CAVITIES

□No faults, except one vacuum trip related to HOMs excitation during tests.

□LLRF

□No faults.

Overview/Booster/SR-60 kW/SR-150 kW/Conclusions

□ 150 kW PLANT (SECTION 9):

- Installed in 2006.
- Elettra type cavity (upgraded type).
- 150 kW amplifier.






- The 150 kW power amplifier is made combining two 80 kW transmitters.
- It has been acquired as a turn-key system from industry (Electrosys).
- The final stage of each transmitter is a 80 kW IOT (TH 793 from THALES).
- HV POWER SUPPLY (for each tube):
 - Switched mode power supply
 - 37 kV, 3.8 A.
- Power supplies specified with redundancy.
- Each transmitter is completely independent to allow standalone operation.
- The transmitters are combined by means of a switchless combiner.

- ❑ Installation took place during Summer 2006
- ❑ Operation on the machine started in Jan.07, after 24 hours/day -2000 hours test at levels from 100 to 150 kW.
- ❑ Power was limited to 60 kW for 2007 (cavity conditioning to be completed).

Output power	150 kW
Frequency	499.654 MHz
Bandwidth (± 0.5 dB)	$> \pm 2$ MHz
Total gain	69.3 dB
Gain IOT A	24.0 dB
Gain IOT B	24.1 dB
I.L. combining system	< 0.1 dB
Total phase variation	11 degrees



- **EXPERIENCE WITH THE NEW PLANT (NOW AROUND 11000 HOURS OF OPERATION).**
- Operation of the new system has been **very reliable (no faults) till middle September 2007** (i.e. roughly 5000 hours of machine operation).
- **From September we started having problems first in TXA and then also in TXB.**
- Generally they are random trips and the system can be restarted immediately.
- If the rate of trips increase, we are required to switch the transmitter to the combiner load and power the cavity with the other transmitter only.
- Since we do not need all the power for the beam yet, we can operate also with one tube.
- **Flexibility of the layout has greatly helped in minimising downtime.**

□ **WHAT WE HAVE LEARNED UP TO NOW AND WHAT WE HAVEN' T YET.**

- Trips are detected as **a fast increase in beam current** as if there were a discharge (HV inhibit) or as an overload in the HVPS.
- They happen only when RF drive is provided.
- **HV inhibit faults do not seem related to the power level** or to particular operating conditions.
- **Few of the faults could be related to machine beam dumps** (some of the ones related to overload in HVPS).
- We tested the HV capability and we did not find problems with the input cavity. Anyway, still under discussion if the problem starts in the tube or in the cavity.
- **In case of high failure rate, this could be generally recovered following a high voltage reconditioning or grid cleaning procedure.**
- However the final effect could be an arc on the ceramic with possible damage of the tube. Most probable in the lower part of the output window.

□NEXT STEPS.

- We have decided to change the tube and circuit assembly type.
- We will install one TH 793-1 in circuit assembly TH 18793 LS, i.e. the ones developed for ALBA.
- The new tube will be installed in **the next shutdown (middle October 2008)**.
- No need to modify the power supplies or solid state amplifier.** The HV and ancillary supplies are ok for the new tube.
- Modifications are mechanical:**
 - Rotation of the output lines, to shift trolley position inside the cabinet.
 - Change of the output line to 6 1/8".
 - Additional water cooling.



□CAVITY

- Conditioned in December 2007 up to 62 kW.
- Installed the new WG to coaxial transition.
- New diagnostics:
 - Arc detection in the coaxial part of the coupler (air-side).
 - HOM interlock board: developed, to be tested with beam.

□LOW LEVEL ELECTRONICS

- Still the original one with few modifications for the control and interlocks of the new plant.
- It works very reliably.
- We will modify the amplitude loop to avoid the risk of fast increase of driving power to the IOT in case of beam dumps.



□ **BOOSTER AND 60 kW SR PLANTS ARE WORKING RELIABLY.**

□ **150 kW NEW PLANT:**

□ Percentage of machine downtime due to the new plant is 6.5 % of the total machine downtime in 2008 up to now (the contribution of the other three plants is 0.5 % totally).

□ **Reliability aspects must be understood and improved** in collaboration with manufacturers.

□ **NEXT STEPS:**

□ Installation of the new IOT.

□ **Test with higher power of the WG to coaxial transition.**

□ Implement HOM board.

□ **NEW PROJECTS:**

□ **Development of a prototype of digital low level RF.**