





Paco Sanchez, RF Group, CELLS

(Consortium for the Exploitation of the Synchrotron Light Laboratory)



New 90 kW IOT for ALBA

- Introduction. The ALBA RF Transmitter
- 2. New IOT at 500 MHz, 90 kW-cw
 - a) Tube Improvements
 - b) Cavities Modifications
 - c) IOT Simulations
 - d) Factory Tests
 - e) IOT Characterization
 - f) Tests in the ALBA RF Lab
- 3. Conclusions




Introduction

ALBA RF Parameters:

	STORAGE RING	BOOSTER (at 3 GeV)				
Frequency	499.654 MHz	499.654 MHz				
RF total Voltage	3600 kV	900 kV				
Beam Current	400 mA	2 mA				
Total Beam Power	540 kW	1.3 kW				
Losses (including IDs)	1300 keV/turn	627 keV/turn				
Type of cavity	NC EU-Cav (DAMPY)	NC 5-cell				
Number of cavities	6	1				
RF Voltage per cavity	600 kV	900 kV				
RF Power per cavity	150 kW	30 kW				
RF Transmitter	2 x 80 kW	1 x 80 kW				
Synchrotron frequency	9.3 kHz	8.6 kHz				



- > 1 RF plant in the Booster (80 kW) + Lab
- 6 RF Plants in the SR (6 x 150 kW)
- Each SR Plant consists of:
 - 2 RF Amplifiers combined through CaCo
- The ALBA RF Tx:
 - HVPS (-36 kV, 3.3 A)
 - IOT (500 MHz, 90 kW cw)
- ALBA will have a total of 14 RF Tx






- New RF Transmitter developed in collaboration between:
 - <u>THOMSON Broadcast & Multimedia</u> in Turgi (Switzerland)
 - ✓ Each IOT is powered by a single HVPS
 - ✓ HVPS based on Pulsed Step Modulators (PSM)
 - ✓ Variable Switching frequency [0.05 12 kHz]
 - ✓ Control system on PLC, interfacing with Tango
 - <u>THALES Electron Devices</u> in Thonon (France)
 - ✓ New IOT (TH793-1) operational at 500 MHz, 90 kW-cw
 - ✓ Adapted Output Cavity (TH18793 LS) to coax 6 1/8"
 - ✓ Bandwidth = 7 MHz
 - ✓ Tuning range = ± 5 MHz
 - ✓ Optimized cooling system
 - <u>CELLS ALBA</u> in Cerdanyola (Spain)
 - ✓ CST-Microwave Studio Simulations
 - √ IOT improvements
 - ✓ Output cavity coupling loops






One HVPS per IOT, based on PSM technology (Pulsed Step Modulation):






HVPS cabinet












The ALBA RF Tx - HVPS

New PSM module design and developed by THOMSON BM



- 60 modules switching at f = 1.67 KHz (modifiable via sw, 0.05 12 kHz)
- $V_{out} = -38 \text{ kV}$ and $I_{out} = 4 \text{ Amps}$
- Redundancy: 700V per mod → 52 modules are enough for -36kV (IOT)



The new IOT 90 kW-cw: TUBE

- Tube Modifications (TED):
 - 1. Bigger output window diameter
 - Conical insulator between grid and anode
- Advantages
 - 1. Better suited for High Power cw operation
 - 2. Electric Field in the ceramic insulator decreased
 - 3. Losses also decreased
 - 4. Less stray electrons impinge on the tube
- Drawback
 - 1. Dedicated product for monofrequency applications



80 kW version (TV) 90 kW version (LS)



The new IOT 90 kW-cw: CAVITIES



Output Cavities Modifications (TED-CELLS):

- 1. Enlarge coax output coupling from 4-1/16" to 6-1/8"
- 2. Redesigned primary cavity to house the new tube 90 kW
- 3. Increase the secondary output cavity depth
- 4. Add a post (resonance vs. harmonics)
- 5. Second arc detector

Advantages

- 1. Cope with the higher cw power operation
- 2. Simplified tuning devices in primary cavity

Drawback

1. Dedicated product (500 MHz)



The new IOT 90 kW-cw: CAVITIES




- Other Modifications (TED-CELLS):
 - 1. Modify accordingly the cavities coupling loops:
 - Output loop
 - Prim-sec cavity loop
 - 2. Water cooling added:
 - Primary cavity
 - Inter-cavity loop
- Advantage
 - 1. Prevent thermal frequency shifts
- Drawback
 - 1. Add water cooling circuits in the RF Tx



The new IOT 90 kW-cw: SIMULATIONS


- Cavity Simulations (CELLS):
 - CST-Microwave Stutio ™
 - Output circuit simulated to obtain the cavities' dimensions and the coupling loops' dimensions
 - 3. Conductive material in the drift tube gap to simulate the beam
 - 4. Material conductivity adjusted in order to get the beam voltage at 90 kW
 - 5. Bandwidth evaluation from the S₁₁ parameter






The new IOT 90 kW-cw: SIMULATIONS

Computed BW compared to the measured one:







The new IOT 90 kW-cw: FACTORY TESTS

- > Tested at 90 kW during ½ hour
- > Duration test, at 80 kW, during more than 24 h, at TED premises
- > Problem on IOT SN 499413 Ionic Pump, solved reconditioning it
- ➤ Bandwidth = 6.8 MHz; and Tuning capabilities = ± 5 MHz
- Efficiency and Gain measured as shown below


HV [kV]	Beam I [A]	Pout [kW]	Eff [%]	Gain [dB]
-36	3.18	80	69.9	23.8
-36	3.31	85	71.3	23.7
-37	3.42	90	71.1	23.9

Harmonics at Dir-Coupler (6" coax output):

Pout [kW]	H2 [dB]	H3 [dB]	H4 [dB]	H5 [dB]
80	-37.5	-62.7	-52.2	-64.0



The new IOT 90 kW-cw: CHARACTERIZATION





The new IOT 90 kW-cw: Operating Hours

Item	IOT S/N	Туре	Manuf.	in Transmitter	Since	Fil Hours	HV Hours	Until	Fil Hours	HV Hours	Filament Hours	HV Hours	Comments
IOT_A001	591095	TH793	TED	Tx01 - ANNA	08/Aug/2007	0	0	11/Dec/2007	150	106	150	106	Considering also FAT hours. IOT returned back to TED
IOT_A002	499413	TH793-1	TED	Tx01 - ANNA	12/Dec/2007	150	106	01/Oct/2008	334	258	184	152	
IOT_A003	499443	TH793-1	TED										Spare Stored
IOT_A004													
IOT_A005						1							
IOT_A006													
IOT_A007													
IOT_A008													
IOT_A009													
IOT_A010													
IOT_A011						نسطال							
IOT_A012													
IOT_A013													
IOT_A014			the same of										
IOT_A015		The state of the s											
IOT_Annn													
- //	1	-								•			

TED THALES Electron Devices

TOTAL Hours



CONCLUSIONS

- The ALBA Tx (new IOT and PSM modules) working reliably in the ALBA RF Lab since December 2007
- HVPS is stable enough at full power 80 kW cw, even with pulsed power during cavity conditioning
- HVPS assures redundancy (2 modules failed during commissioning, keeping the HVPS operational)
- IOT safe operation at ALBA full power (80 kW): factory tested at 90 kW
- > IOT bandwidth large enough
- IOT efficiency and gain have been improved with respect to the standard IOT



Acknowledgements

I would like to take this opportunity to thank:

THOMSON Broadcast & Multimedia – Jurgen Alex, Andre Spichiger, Jan Stahl

<u>THALES Electron Devices</u> – Pascal Ponard, Claude Bel, Guy Peillex-Delphe

CELLS - ALBA – Francis Perez, Michel Langlois

for their contributions to this new RF Transmitter.



Many thanks for your attention



To update and share (4 times per year?)

Item	Laboratory	Manuf.	Туре	IOT S/N	f [MHz]	P [kW]	η [%]	G [dB]		Operating Until	Filament Hours	HV Hours	Comments
IOT_A001	ALBA	TED	TH793-1	499413	500	60	64	24,7		01/Oct/2008	184	152	Still in operation
IOT_A002	ALS	CPI			500	30						10000	Several trips after shutdown periods: operate daily 3-4 h
IOT_A003	BESSY-MLS	CPI			500	40							
IOT_A004	DIAMOND	TED	TH793		500	30							
IOT_A005	DIAMOND	TED	TH793		500	30							
IOT_A006	DIAMOND	TED	TH793		500	30							
IOT_A007	DIAMOND	TED	TH793		500	30	4						
IOT_A008	DIAMOND	e2V			500	30							
IOT_A009	DIAMOND	e2V			500	30							
IOT_A010	DIAMOND	e2V			500	30							
IOT_A011	DIAMOND	e2V			500	30							
IOT_A012	ELETTRA	TED	TH793		500	30						5000	
IOT_A013	ELETTRA	TED	TH793		500	30						11000	
IOT_A014													

