




PETRA III, A New High Brilliant Light Source At DESY

- Objectives & Key parameters
- Conversion of PETRA II into PETRA III
- Commissioning Results
- Summary


Projects & Plans



PETRA III

A Low Emittance
Synchrotron Radiation Source

Technical Design Report



DESY 2004 - 035


February 2004

Parameters:

- circumference: **2304 m**
- energy: **6 GeV**
- emittance: **1 nmrad**
- emittance coup.: **1% (10 pmrad!)**
- current: **100 (200) mA**
- # bunches **40 / 960**
- straight sections: **9**
- undulators: **14**
- undulator length: **2, 5, 10 (20) m**
- supplement to X-FEL
- ➔ cost effective!

PETRA III


Modernization & refurbishment



New coils



New
cooling



New power supplies, new control system, new vacuum system,...

Installation in old octants

Installation of new water pipes



Installation of refurbished dipoles Including vacuum chamber...



Installation of Quadrupoles, Sextupoles & Vacuum chambers Start: 19.11 ...




**Installation finished middle
of 2008**

Layout of the new hall

At the outer perimeter preparation labs and infrastructure installations are foreseen

PETRA III will provide 9 straight sections for insertion devices. 5 of them will be equipped with 2 canted undulators each, resulting in 14 independent beamlines



The ring tunnel and the experimental floor are founded on a **1 m thick slab of concrete** to minimize vibrations. For vibrational decoupling, the building superstructure rests on **20 m long sleeved piles**

New Experimental Hall



Building of the concrete slab



New Experimental Hall

Middle of 2007 ...


Middle of 2008 ...



PETRA III




new experimental hall

undulators: $5 \times 2\text{m (canted)} + 3 \times 5\text{ m} + 1 \times 10\text{ m} = \underline{14}$



- angular offset: **5mrad**
- undulator length: 2 times **2m**
- beam separation at shielding wall: **~15cm**
- ➔ independent beam shutters and safety systems


Aufbau DBA Zelle (# 8)



Undulators

Undulator PU 10

Undulator PU 8 & 9



8 of 14 Undulators
have been installed

Optics & experimental hutches



PETRA III: $\varepsilon_x = 1$ nmrad

$\varepsilon_x = 6$ nmrad @ 6 GeV
(PETRA II low emittance lattice)

$\varepsilon_x = 4.5$ nmrad @ 6 GeV
(PETRA II low emittance lattice & new octant)

$$\mathcal{E} \propto f(\phi) \cdot \theta^3$$

Possibilities:

- designing new optics with *existing magnet hardware (TME) (B)*
- designing new optics with *new magnet hardware (FODO 90° shorter dipoles) (C)*
- designing new optics with *existing magnet hardware and use of damping wigglers (A)*

PETRA III :damping wiggler

$\varepsilon_x: 4.5 \rightarrow 1 \text{ nmrad}$

Damping wiggler sections



Collaboration with BINP



Damping wigglers

- $B = 1.5 \text{ T}$
- $\lambda = 0.2 \text{ m}$
- $h = 0.025 \text{ m}$
- $L_{\text{tot}} = 80 \text{ m (2x40m)}$

Damping Wigglers




- **Modified hybrid structure**
poles also powered from aside
- **Iron plates enclose the whole structure**
act as magnetic yoke on zero magnetic potential
serve as mech. support for magnetic assembly
- **compact, and mechanically stable design**
cross section $\sim 260 \times 290 \text{ mm}^2$
- **easy and cheap**

Wiggler Section


440 kW @ 200 mA, $\epsilon_c = 36$ keV

Opening angle: 5 mrad horizontal, 0.085 mrad vertical






Damping Wiggler Sections

Both sections completely installed.
All wigglers moved in



Damping Wiggler Sections










First beam through transferline on **24.03**

Optics about correct, i.e. measured profiles agree with theoretical within 10%

Stored beam

Beam was stored on **April 13** (one bunch with 20 μA i.e. about 10^9 e+)
RF – phase right and orbit empirically corrected in the new octant




First Light on April 30

First light on April 30:

- Undulator PU 9 (OL 142m)
- Single bunch 0.5 mA
- Gap closed to 10 mm (foreseen 9.5)
- No effect on machine (orbit / tune)
- Beam centred with horizontal and vertical Bumps
- Power up to 8W


Picture at screen monitor at 28 m
With corrections




30.09.2009

PETRA III

Screen monitor at 17.5 m



Screen monitor at 28m



Balewski - MPE

23

PETRA III

current limitations

- **Multibunch instabilities are a problem:**
Situation **PETRA II**


	longitudinal	horizontal	vertical
I_{thres} (mA)	7	6	6
$1/\tau$ (Hz)	35	50	60
Z_{eff}	3.6 M Ω	45 M Ω /m	54 M Ω /m

PETRA III: 12 instead of 16 cav. & larger long. (radiation) damping


→ powerful broadband ($BW \geq 60\text{MHz}$) feedback necessary

Status Multibunch Feedback


- Installation complete
- Electronics housed in special climatized huts
- PETRA II MB-Feedback reinstalled to ease commissioning




Current limitations multibunch



Design: 100 mA
70 bunches: 67 mA
960 bunches: 60 mA



emittance





- gefittete horizontale Strahlfleckgroesse: 42.7 μ m (1sigma-Breite)

Annahme:

- $\beta_x = 1.6\text{m}$
- $D_x = 1.3\text{cm}$
- $\Delta(p)/p = 1.3\text{E-}3$

=> **emittanz x = 0.96 nm rad** (GROBABSCHAETZUNG,
lousy lifetime for I = 1.4 mA => $\tau = 1.5\text{h}$



Orbit stability goal

$\varepsilon_x = 1 \text{ nmrad}$ coupling 1%

	Low β insertion			High β insertion			
	$\beta(\text{m})$	$\sigma(\mu\text{m})$	Amplification factor	$\beta(\text{m})$	$\sigma(\mu\text{m})$	Amplification factor	
Horizontal	1.19	34.6	17.25	19.84	141	70.24	
Vertical	4.0	6.3	34.08	2.37	4.9	26.20	

Stab. Requirement $0.1 * \sigma$
→ Sub micron orbit stability !!


Status orbit feedback

- air coils installed in tunnel
- installation of electronics in climatized huts



Orbit stability (preliminary results)

Micrometer scale!!



Summary

Parameter	Design	Achieved
Energy (GeV)	6	6
ε_x (nm rad)	1	1
ε_y (pm rad)	10	< 50
Current (mA)	100	67
Orbit stability	10% of beam size	Work in progress
# undulators	14	8

10 more weeks for commissioning until December 21-st

User operation starting in February next year

**Thank you for your
Attention!**