SRF Operation Status of SSRF

Jianfei LIU

RF Group Shanghai Institute of Applied Physics Email: LIUJF@SINAP.AC.CN



Shanghai Institute of Applied Physics, Chinese Academy of Sciences



Contents

Overview of Shanghai Light Source (SSRF)

- Booster's RF System
- Storage Ring's SRF System
- Cryogenic System
- Operation Status of SRF System









The Location of SSRF Site in Shanghai

SINAP















Layout of the SSRF complex





SSRF Booster

- Full energy booster ,optimized for topup injection;
- Two super-fold and 28 cells FODO with 8 missing dipole magnets;
- Beam emittance about 100 nm-rad @3.5 GeV for clean top-up operation;
- □ A circumference of 180m and a injection energy of 150MeV;
- **Repeat rates up to 2Hz;**

Booster Layout







Storage Ring Main paramaters: Energy: 3.5 GeV; **Circumference:** 432m; **Current:** 5/300 mA (S/M bunch); **Demittance: 3.9 mm-mrad; Strait section:** 4*12m, 16*6.5m; **RF** voltage: 4-6 MV □Max Power: ~600kW **Orbit Stability:** <10% beam size



Contents

Overview of Shanghai Light Source (SSRF)

- Booster's RF System
- Storage Ring's SRF System
- Cryogenic System
- Operation Status of SRF System

The layout of the booster RF system



- 1. One 180KW transmitter feeds power to two normal conducting 5cell cavities, ramping energy from 150 MeV to 3.5 GeV, and its LLRF is analog I/Q from ACCEL company.
- 2. It has been commissioned successfully in June of 2007



Measured parameters of booster cavities

| Parameter | Specified Value | Measured cavity1/cavity2 | Unit |
|------------------------------|-----------------|----------------------------------|-------|
| Resonant frequency | 499.654(30°C) | 499.747(19°C)/499.749(18.7°C) | MHz |
| Coupling factor | 1~1.2 | 1.092/1.068 | |
| Unload quality factor | >29000 | 29618/29386 | |
| Tuning-range | >+/-0.2 | +0.9325/-0.2537, +0.9337/-0.2450 | MHz |
| Tuning-precision | <100 | 2.08Hz/2.13 | Hz |
| Tuning-speed | >1 | 2.773/2.80 | kHz/s |
| Field flatness at 499.654MHz | <+/-5 | <+/-1 | % |

Main Designed and Measured Parameters of Booster RF System

| Parameter | Value | Unit |
|--|---------|------|
| RF frequency | 499.654 | MHz |
| Beam energy | 3.5 | GeV |
| Energy loss per turn | 0.915 | MeV |
| Single/Multi-bunch mode beam current | 2/10 | mA |
| Beam power (Multi-bunch) | 9.15 | kW |
| RF voltage | 1.80 | MV |
| RF Phase Stability | <±1 | 0 |
| RF Amplitude Stability*(*Ramping) | <±1 | % |

The achieved parameters of booster RF system

| Mode | Phase(close loop) | Amplitude(close loop) |
|--|--|-----------------------------------|
| CW(0.1MV) | Peak-to-peak = 2.5° ; RMS= 0.5° | Peak-to-peak=4.8%; RMS= 0.96% |
| CW(2MV) | Peak-to-peak = 0.5° ; RMS= 0.1° | Peak-to-peak=0.35%; RMS= 0.07% |
| Ramp(0.1 MV~2 MV) (8 Hours stability) | Phase stability : 0.17° RMS | Amplitude stability : 0.2% RMS |



Contents

Overview of Shanghai Light Source (SSRF)

- Booster's RF System
- Storage Ring's SRF System

Cryogenic System

Operation Status of SRF System



Main requirements of SRF for SSRF storage ring

| RF frequency | 499.654 MHz |
|-------------------------------|-----------------|
| RF voltage | ≥4.0MV (5.0MV*) |
| RF phase stability | ≤±1° |
| RF amplitude stability | ≤±1% |
| Beam power | 491 (625*) kW |

The layout of the storage ring SRF system







Main parameters of the 350 kW loads:Average power350 kW CWReturn loss> 30 dB

Main parameters of Klystrons : RF output power: > 300 kW CW RF drive power: < 31 W Instantaneous bandwidth (-1 dB): > 2 MHz Gain: > 40 dB Efficiency: > 63 %



Main parameters of the circulators:

Forward power350 kW CWReflected power at any phase350 kW CWInsertion loss at center frequency > 26 dBInsertion loss in bandwidth> 20 dBIsolation at center frequency> 26 dBIsolation in bandwidth> 20 dBReturn loss at center frequency> 26 dBReturn loss in bandwidth> 20 dBReturn loss in bandwidth> 20 dBHandwidth> 20 dBReturn loss in bandwidth> 20 dBHandwidth> 20 dBHandwidth+/- 2 MHz

── 中国科学院上海应用物理研究所

FAT of Klystrons





中国科学院上海运用物理研究所 Shanghai Institute of Applied Physics.

Milestone of RF Transmitters

| (P) | June-July 2005 | Call for tender |
|---------|----------------|-----------------------------------|
| () | Sept. 2005 | Contract for RF power system |
| (P | Feb. 2006 | Final design review of amplifiers |
| (P | Oct. 2006 | FAT of 1st klystron |
| (P) | Feb March 2007 | SICAT of 1st amplifier |
| () I | March 2007 | Test of 1st circulator |
| (P) | April 2007 | FAT of 2nd & 3rd klystron |
| (F | July-Oct. 2007 | SICAT of 2nd & 3rd amplifiers |
| (B) | Oct. 2007 | Test of 2nd & 3rd circulators |

Chinese Academy of Sciences





KSU installation and commissioning



Results of SAT of 3 sets of 300 kW RF Amplifiers





1.07E9 @ V_{acc} =3.05MV

5.88E8 @ V_{acc} =2.86MV

7.88E8 @ V_{acc} =2.84MV

0.1

#1

#2

#3

1.45E9 @ V_{acc} =2.13MV

1.07E9 @ V_{acc} =2.0MV

1.52E9 @ V_{acc} =2.04MV

4.0

J.-F. LIU ESLS KF 2009

Horizental Tests on SSRF Site









| | Parameter | | Μ | asured value | | |
|---|-------------------------------|-------------------|------------|--------------|---------|--|
| | | Guarante Value | M#1 | M #2 | M #3 | |
| P | Q _{external} | 1.7 E5 +/- 0.3 E5 | 1.6E5 | 1.78E5 | 1.75E5 | |
| | V _{acc} | > 2.0 MV | 2.1 MV | 2.03 MV | 2.02 MV | |
| | P_{diss} @ Vacc = 2MV | < 70 W | 60 W | 46 W | < 55 W | |
| | Static losses | < 30 W | < 30 W | < 30 W | < 30 W | |
| 9 | Total losses @ Vacc = 2MV | < 100 W | < 90 W | < 80W | < 85 W | |
| | RF in SW off resonance | 120 kW | 110 kW* | 120 kW | 120kW | |





Leakage Happened During Shipping







June 6, 1st Module SAT Aug. 3, 2nd Module SAT Sept. 13, 3rd Module SAT



At July 1st, two sets super. cond. modules were installed to the final location in tunnel









From Sept. 17, 3 sets superconducting modules have been put into operation.





SINAP has successfully developed its own digitalized LLRF system. Its operation was stable and reliable both for backup system and superconducting modules.









Stability of Amplitude and Phase with SC



| RF frequency | 499.654 MHz |
|------------------------|-----------------|
| RF phase stability | <u><+1</u> ° |
| RF amplitude stability | ≤±1% |



Contents

Overview of Shanghai Light Source (SSRF)

- Booster's RF System
- Storage Ring's SRF System

Cryogenic System

Operation Status of SRF System

Cryogenic System

Courtesy of Cryogenic Group





Contents of Cryo-plant Specifications of Cryogenic System Flow Diagram of Cryogenic System Layout of Maim Equipments Commissioning and Test Results Milestones of Cryo-plant





Specifications of Cryogenic System

- Capacity of cryogenic plant Refrigeration mode: ≥ 650 W/4.5K ≥ 600W/4.5K (In normal operation condition)
- 2. Pressure fluctuation in LHe dewar: $\leq \pm 3.0$ mbar
- **3.** Helium level fluctuation in the dewar: $\leq 1\%$
- 4. Continuous operation time: > 8000 hours



4K Cooling Requirements from SRF Cavities

| | Static load | $3 \times 30 \text{ W} = 90 \text{ W}$ | |
|---------------------------|-----------------|--|--|
| Three Cavity Cryostats | Dynamic load | $3 \times 70 \text{ W} = 210 \text{ W}$ | |
| Cryostats | Cooling coupler | 3×4 L/hr =12 L/hr | |
| MCTL | | 17.5 W | |
| MCTL (Air Liquid supply) | | 5 W | |
| SCTL (Rigid section) | | 18 W | |
| SCTL (Flexible section) | | 6 W | |
| 2000L dewar | | 20 W | |
| Valve Box | | $3 \times 10 \text{ W} = 30 \text{ W}$ | |
| Total | | $397 \mathrm{W} + 12 \mathrm{L/hr} \approx 440 \mathrm{W}$ | |
| Safety margin | | $650W/440W \approx 50\%$ | |

Courtesy of Cryogenic Group

中國科学院上海走的物理研究所 Shanghai Institute of Applied Physics, Chinese Academy of Sciences

Flow Diagram of Cryogenic System




Layout of Main Equipments





The Cold Box of HELIAL2000 and the 2000L dewar



HELIAL refrigeration system is based on a 2-turbine-inseries Claude cycle which is a combination of a Brayton and Joule Thomson cooling cycle.

HELIAL is a full automatic refrigerator.



Main Parameters of HELIAL 2000

| Cooling Capacity | 650 W @4.5 K |
|-----------------------------|-----------------|
| HP | 13.43 bara |
| LP | 1.2 bara |
| He mass flow rate | 100 g/s |
| LN ₂ consumption | 5.6 g/s |

Main Parameters of 2000L LHe Dewar

| Capacity | 2000 L |
|-----------------------------|--------------|
| Boil off rate | < 1 % |
| Electrical heater power | 700 W |
| helium level fluctuation | ± 3 mbar |

Note: With LN₂ Precooling





Compressors and Oil Removal System





Main Parameters of Compressors

| Function | M | Recovery | |
|---|-----------|-----------|-----------|
| Model | ESD 441 | CSD122 | ASD 57 |
| Mass fow rate (g/s) | 80 | 21 | 9.4 |
| Suction pressure (bara) | 1.05 | 1.05 | 1.05 |
| Discharge pressure (bara) | 15 | 15 | 15 |
| Electrical motor rating (kW) | 265 | 75 | 30 |
| Cooling water consumption (m ³ /h) | 25 | 4.3 | |
| Cooling air consumption (m³/h) | 9500 m3/h | 1400 m3/h | 5300 m3/h |
| Other | VFD | | |





Gas Yard Area





Parameters of GHe Storage Tanks

| Quantity | 4 |
|---------------------|--------------------|
| Capacity | 100 m ³ |
| Design pressure | 1.8 MPa gauge |
| Working pressure | 1.35 Mpa gauge |
| Working temperature | -10~70 (°C) |

Parameters of the LN₂ tank

| Capacity | 40 m ³ |
|---------------------|--------------------|
| Design pressure | 0.8 MPa gauge |
| Working pressure | 0.08~0.4 MPa gauge |
| Working temperature | 77~350 K |
| Boil off rate | < 0.5 % |



Multi Channel Transfer Line





Bird view of Multi Channel Transfer Line





Commissioning and Test Results

Capacity measured at the main dewar

| Operation | Heat Power | Operation time | Equivalency | Design |
|-----------|--------------|----------------|-------------|----------|
| condition | In the dewar | | Capacity* | Capacity |
| Maximum | 635W | 8 hours | 657W | 650W |
| Normal | 603W | 72 hours | 625W | 600W |

*Equivalency capacity = Heat power + Heat leak of the dewar and transfer line.

Stability measurement

| | Design value | Test result |
|-----------------------------------|--------------|----------------|
| Suction line pressure fluctuation | ± 3 mbar | ± 0.3 mbar |
| Main dewar pressure fluctuation | ± 3 mbar | ± 0.2 mbar |
| He Level fluctuation | ±1 % | ±0.3 % |



Courtesy of Cryogenic Group





Capacity test result

Operation with three cavities (Aug. 1, 2008)



Courtesy of Cryogenic Group





Milestones of Cryogenic System

A emergency backup rf system was launched up in the middle of October 2007 by **RF Group**

| •Nov. | 2005 | Contract the refrigerator to Air Liquide | |
|-------|------|--|--|
| •Feb. | 2007 | Installation of the refrigerator | |
| •Nov. | | Installation of the MCTL | |
| •Apr. | 2008 | Acceptance of the refrigerator | |
| •Jun. | | Cooling down the first SRF cavity | |
| •Aug. | | Operation with two cavities | |
| •Sep. | | Operation with three cavities | |



GHe Transfer Line (Installed in the No2. Underpass)

4 cavities Rent from PF of KEK



At Dec. 12, 2007, 3 sets normal cavaties

A installed Supercon. Cavity Was Removed from the Tunnel in Nov. 2007

June 20, 2008, NC cavities operated for 6 months was removed and replaced with two SC modules



With 3 sets Normal Cavities, we successfully got:
3.0GeV Commissioning,
100mA@3.0GeV,
200mA@2.0GeV,
300mA@1.5GeV



Contents

Overview of Shanghai Light Source (SSRF)

- Booster's RF System
- Storage Ring's SRF System
- Cryogenic System

Operation Status of SRF System in SSRF

本 論 科 等 法 法 海 法 治 物 渡 研 索 形 Shanghai Institute of Applied Physics, Chinese Academy of Sciences 27/12/2008 Beam Current 224mA





5/7/2009 Beam Current 252 mA





18/7/2009 Beam Current 300mA --the Maximum Designed Beam Current--





- •Machine protection signal
- •Temperature interlock on beam tube FBT and RBT



- **>** Scheduled Operation Time 5300 hours
- **Break-down:** 437.8 hours
- Machine shutdown : 3050.5 hours
- **For Beamlins commissioning : 1152 hours**







中国科学院上海应用物理研究厅

The Ratio of Break-down Time January ~ April 2009

- **For Beamines Commissioning: 1263 hours**
- Machine Study: 948.6 hours, Faults: 5.5%
- Hardware Faults: 121.75 hours
- Machine Shutdown: 546.7 hours
- > Availabilty 96%



| PB# | 1: Trips | RF trips other than vacuum (3 cavities) | | | | | | |
|--|------------------|---|---------|---------------------|--------|--------|-----------|---------|
| Vacuum near by | | r by | | Transmitters' fault | | | LLRF down | unknown |
| RFV | Vindow | | 6 weeks | weeks 4 | | | 1 | 2 |
| | | | C#1 | | C#2 | C#3 | | 2 |
| Date | | C#1 Total | MS time | SR time | Vacuum | Vacuum | | • |
| 1st week | March 3-14 | 8 | 4 | 4 | 0 | 0 | | |
| 2nd week | March 15-21 | 3 | 2 | 1 | 0 | 0 | | |
| 3rd week | March 22-28 | 2 | 1 | 1 | 0 | 0 | 11000 | 2 |
| 4th week | March 29-April 4 | 7 | 6 | 1 | 0 | 0 | | |
| 5th week | April 5-11 | 4 | 3 | 1 | 0 | 0 | | |
| 6th week | April 12-18 | 2 | 1 | 1 | 0 | 0 | | |
| 1, Cavity #2 & #3 from July, C#1 from Sept. 20 2, Once standby at 4.5 K because of its tuner 3, Parameters not optimized 4, Aging not enough (Window) 5, Bad lucky of its location just after the bending magnet | | | | | | | | |











Trip diagnostic system



| 1504 | | | | | ceffected power | <u>~</u> |
|------------------------------|--|---------------|---|------------------------|--------------------|--------------------------|
| | 10:52:21.9900 | 1 | 1 | 2.000 ms/div | 1 | 10:52:22.0020 |
| Page 1 | | ···· > (-)(-) | | X=10:52:22.0000384 | 4.839280 mSec | conds> Y=1.444829 V |
| _ | Contraction of the local division of the loc | | | - 1.000 - H Jan - | | 2 |
| Zoom | | | | 0 | bit | Ť. |
| ISO10 | | | | | | |
| 15012 | | | | | | |
| 15013 | | | | For | ward power | |
| ISO14 | | | | Refl | ected power | -~ |
| | 10:52:21.9909 | | | 2.000 ms/div | 1 | 10:52:22.0020 |
| Page 2 | | ···· > 💿 😁 | | X=10:52:21.9998230 | AX=4.619013 mSec | Y=-9.520719 mV |
| Zoom | | | | 1.000 myon | | 1 00.27.22 |
| ISO9 397.1 mV 399.4 mV | | | | | | |
| ISO10 1.457 V 1.434 V | | | F | | | |
| 15011 1.453 V 1.214 V | | | | Reflected power | | |
| 3/29/2009 | 1 02:52:02.7525 | | | 2.000 ms/div | | 1 02:52:02.7680 |
| Page 2 | | > 📀 🎯 | | X=3/30/2009 02:52:02.7 | 625861 🔁×=4.765659 | 9 mSeconds> Y=1.452770 V |

Active Recording: beamtrip090329001.lrf User Mode: Review

2009-06-19-16pm: Cavity #1 quench first





Further SRF system commissioning







Power of HOM and absorber



PB#5: IF Cryo-plnat is shutoff by Elec or others, what can we do? Just watching?

Twice happened since Jan. 2008



Electricity was off, cryoplant was down suddenly, return lines of helium vessel were closed. IS THERE OTHER BETTER SOLUTION except watching?

NEXT STEPS

Shanghai Key Lab for Cryogenics & SRF Technology



NEXT STEPS Shanghai Key Lab for Cryogenics & SRF Technology

















J.-F. Liu ESLS RF 2009

NEXT STEPS Shanghai Key Lab for Cryogenics & SRF Technology



- 1. MgB2 cavity to be studied
- 2. Single Cell 500MHz Cryo-Module as a spare one (Budget is READY)
- 3. Multi Cell 500 MHz Cryo-Module for Prototype of ERL (Building is under construction)


