


PAUL SCHERRER INSTITUT



SwissFEL



Wir schaffen Wissen – heute für morgen

Paul Scherrer Institut Status and Progress at SLS and SwissFEL


18.09.2013

Paolo Craievich on behalf of RF group


17th ESLS-RF Workshop, Helmholtz Zentrum Berlin, 18-19 September 2013

- SLS operation statistics in 2012**
- Major failures in 2012 and 2013**
- SLS RF upgrade programs**
 - 500 MHz test-stand
- SLS extraction line**
- SLS upgrade perspectives**
- Status of RF for SwissFEL project**
 - **Building site**
 - **C-band test-stand**
 - **Injector test facility**

SLS Operation Statistics




- ❑ The beam availability in 2012 again reached 98.7%
- ❑ **MTBF was 3.5 days**
- ❑ Number of “incident” about the same as in 2011
- ❑ Beam quality distortions that influence quality of experimental data: significantly improving over past six years
- ❑ **More than 1.5 days between any of these beam distortions**




Ref.: A.Lüdeke et al., PSI annual report 2012

Beam outage count per failure category



- New RF interlock system has helped improvement over last period


- The statistical increase in the number of beam losses by unknown sources was most likely the result of an **upgrade of the RF interlock systems**, which now avoids the false assignment of certain failures to the RF systems



Beam outages per failure category in 2012

Ref.: A.Lüdeke et al., PSI annual report 2012

- ❑ **Reduced beam current of 350 mA** in the first 8 weeks due to coupled bunch mode (+71), causing beam instabilities and sudden beam losses
 - Several unsuccessful attempts were made to tune the higher order modes of the cavities
 - Problem seemed to be resolved by changing the RF frequency slightly
- ❑ **Two new tools for the investigation:** capacitive pickups in the input coupler (already installed) and BPM bellows with SMS feed-through



❑ Shutdowns extensively used for preventive maintenance

- **Six water** leaks in the cavity cooling system were found and sealed during 2012 shutdowns, some leaks that had been sealed with glue several years ago had reopened.
- One water leak came out just after a shutdown. The **48 hours needed to seal this leak** were spent during machine development time and *therefore do not show up in the downtime statistics.*
- In 2008, such interruptions caused a total of **98 hours of downtime.**


❑ In order to achieve a permanent solution for the problem of recurring water leaks in the RF cavities, **it is planned to replace all cavities**

- First one in January after RF conditioning in October

❑ Contamination of heat-exchanger in cryo-plant of S3HC (required warm-up and regeneration during October shutdown) – no downtime

❑ Problems with temperature measurement system of S3HC (5h+3h)

- ❑ **Accumulation issue still due to coupled bunch mode (+71)**
 - Partially solved by applying small phase modulation to the RF accelerating voltage
- ❑ **S3HC: replaced insulation vacuum pump due to defective Maxi Gauge controller (8h)**
- ❑ **Water leak in the RF window on the S-band pre-buncher**
 - Temporary solution: pre-vacuum in the cooling pipe
 - Reforming of the cathode
 - After replacement arcs in the sub harmonic pre-buncher




- ❑ **S3HC: 4 days downtime due to serious Helium contamination**

Accomplished

- Fire protection for LINAC modulators installed
- All storage-ring coincidence arc detectors installed
- Spare 500MHz RF cavities received from ELETTRA
- S3HC spare valve-box constructed at PSI workshop
- All Input Power Coupler replaced
- Bead-pull measurement on first RF cavity
- Support-frame for one Klystron was modified

Work in progress:

- 500 MHz test-stand**
- 60 kW Solid-state amplifier
- Planned to replace one storage-ring cavity per year
- Fire detectors for storage-ring klystron power supplies
- Refurbish Klystrons, optimize efficiency and repair cooling circuit (on going) - CPI
- Spare solenoids for LINAC in construction (expected delivery by 2013)




Motivations:

- ❑ Klystron by EEV is not produced anymore → test of new source
- ❑ Actual storage ring cavities continuously have water leaks
- ❑ Spare part of amplitude, phase and tuning loops are not available anymore

Tasks in the test stand:

- ❑ Nov-Dec 2013: conditioning and test of new input coupler
- ❑ Nov-Dec 2013: conditioning of the first cavity
- ❑ Test of the solid-state amplifier from October 2013
- ❑ Test of the regenerated and repaired klystrons (2014)
- ❑ Test of amplitude, phase and tuning loops (2014)
- ❑ Training gym for picket group




- ❑ Standard Waveguide WR 1800 H-plane 4-Port Motorized Switch
- ❑ Impedance 50 Ω
- ❑ Average power \leq 300kW, Peak power 124 MW
- ❑ Insertion losses \leq 0.02B, VSWR \leq 1.03, Isolation $>$ 70 dB
- ❑ Switching time: 6 s



Coax-to-WG transition (MEGA)

Motivation


- ❑ Direct measurement of beam parameters
- ❑ Comparison with measurements in the storage ring
- ❑ Compact beam line to fit into the existing tunnel (with small extension)
- ❑ In-house experiences on beam measurements from SLS and SwissFEL injector linac



- ❑ Several options under study
- ❑ Need a fast horizontal or vertical kicker and septum
- ❑ Slowest raise time about $1 \mu\text{s}$ for 1 bunch
- ❑ Flat-top flatness not very important

Ref.: M. Aiba et al., Extraction beam line for light sources, IPAC 2013

SLS-2 upgrade dreams




- ❑ SLS emittances : $\epsilon_x = 5.5 \text{ nm}$, $\epsilon_y \sim 1...10 \text{ pm}$
- ❑ Emittance for next generation: $< 1 \text{ nm}$
- ❑ keep all beam lines (ID & bends)
- ❑ re-use girder system and injector complex
- ❑ **emittance 250...400 pm**
@2.4 GeV, in 288 m circumference with 12 straights
- ❑ 5.7 T LGSB (*longitudinal gradient super bend*)
- ❑ small magnet bore $\Phi = 24 \text{ mm}$



**! DRAFT !
feasibility
to be still
verified**


Ref.: A. Struen

S-band injector




C-band main linac

| Key parameters | | |
|--------------------------|-------------------------------|-----|
| Wavelength | 1-70 | Å |
| Pulse duration | 3-20 | fs |
| Beam Energy | 5.8 | GeV |
| Bunch charge | 10-200 | pC |
| Repetition rate | 100 | Hz |
| Slice emittance (design) | 0.18 (10 pC) 0.43 (200 pC) | μm |
| Slice energy spread | 250-350 | keV |
| Saturation length | <50 | m |




- ❑ Construction started in 2013
- ❑ Ground breaking in April 2013
- ❑ Laying of the foundation stone on July 3rd
- ❑ Building handover in December 2014





- ❑ Commissioning planned to start in 2015
- ❑ User operation for Aramis planned in 2017
- ❑ Athos line planned for 2019


SwissFEL C-band test-stand




Ref.: J. Alex and R. Zennaro



- ❑ SwissFEL energy gain requires 28 MV/m @100Hz
- ❑ Actually we have on the first accelerating structure >28 MV/m @ 100 Hz with both phase jump and phase modulation and BDR<1e-6
- ❑ Next step: conditioning of the full C-band module (4 RF structures with pulse compressor).











- ❑ Maximum beam energy 270 MeV
- ❑ Emittance after a full optimization:

| | 200 pC | 10pC | Unit |
|----------------------------|--------|-------|------|
| Projected emittance | ~0.30 | ~0.15 | μm |
| Slice emittance | ~0.20 | ~0.10 | μm |

- ❑ These emittance values fulfill the SwissFEL requirements for **uncompressed beam**
- ❑ X-band system available from April 2013 (**21MV @18MW and 10Hz**)
- ❑ Installation of the new PSI RF gun and undulator experiment in November 2013

Ref.: IPAC 2012 and FEL 2013

SITF: X-band and linearized compression



Thanks for your attention

