

# Welcome to SOLEIL !




Jean-Marc FILHOL

Parameters	Design	Achieved as of Sept 2007
Energy ( GeV )	2.75	2.74
RF frequency ( MHz )	352.197	
Betatron Tunes	18.20 / 10.30	18.2009 / 10.2990
Natural Chromaticities	-53 / -23	-53 / -19
Momentum Compaction $\alpha_1 / \alpha_2$	$4.5 \times 10^{-4} /$ $4.6 \times 10^{-3}$	$4.55 \times 10^{-4} /$ $4.30 \times 10^{-3}$
Emittance H ( nm.rad )	3.73	$3.70 \pm 0.2$
Energy spread	$1.016 \times 10^{-3}$	$1.0 \times 10^{-3}$
Coupling, $\epsilon_V/\epsilon_H$	<1%	0.3% (without correction)
Current Multibunch mode ( mA )	500	300
Average Pressure ( mbar )	$1 \times 10^{-9}$	$3 \times 10^{-9}$
Beam Lifetime ( h )	16 h	9h @ 300 mA / 22h @ 100 mA
Single bunch current ( mA )	12	20
Beam position stability, $\mu\text{m}$ ( H )	20 (rms)	3 ptp
Beam position stability, $\mu\text{m}$ ( V )	0.8(rms)	2 ptp

# Beam Current

The maximum beam current of **300mA** is used routinely (for BL RP control)

300mA →



5 hours

The installation of the second cryomodule is foreseen in spring 2008.  
This will enable to reach **500mA**.


- **Maximum current: 300 mA in 312/416 buckets**
- **Total beam integrated dose: 330 A.h (Sep 2007)**
- **The Beam lifetime for 300 mA in 312 bunches is 9 hours\*, limited by the vacuum ( $3.5 \times 10^{-9}$  mbar).**
- **At 100 mA ( $1.2 \times 10^{-9}$  mbar), the beam lifetime is about 22 hours\*.**

*\*with a coupling of 0.3%.*


- **The injection efficiency is above 90%. We are still working on the objective to maintain this value for the different configurations of Insertion Devices.**

# Beam Emittance


## Pinhole Camera



## Vertical Projection



## Horizontal Projection



$$\epsilon_x \cong 3.7 \text{ nm.rad}$$

$$\epsilon_z^* < 5 \text{ pm.rad} (\kappa < 0.13 \%)$$

$$\sigma_z = 9 \text{ } \mu\text{m} \text{ (including } 5 \text{ } \mu\text{m instrument resolution)}$$


\*: after correction. Before correction  $\kappa$  is around 0.3%.

# Beam position stability

Natural position stability in both planes on 2 BPMs during a 8 hours vacuum conditioning shift.

$\Delta X \sim 25 \mu\text{m}$  ,  $\Delta z \sim 50 \mu\text{m}$

No correction (SOFB OFF)




- ❖ Orbit stability requirements
  - 1/10<sup>th</sup> of beam sizes (H: 20  $\mu\text{m}$  rms, V: 0.8  $\mu\text{m}$  rms)
- ❖ 120 BPMs (Libera Electronics, noise: 0.2  $\mu\text{m}$  rms)
  - 48 fixed on independent support (in Stainless Steel)
  - 72 fixed onto the girders
- ❖ 56 Horizontal and vertical correctors (sextupole secondary coils)
- ❖ RF frequency
- ❖ Algorithm: SVD 56 singular values in both plane
  - Period of correction: 10 s
  - RF correction step-size : 0.3 Hz
  - 5 seconds of BPM average using 10 Hz Libera data flow
- ❖ Noise sources being investigated
  - Booster power supplies
  - Drift with temperature (SR-tunnel temperature regulation)
  - ID motions (electromagnetic, in-vacuum, Apple II types) mainly compensated using dedicated feedforward correctors

# Beam position stability (with SOFB)

on 2 straight sections during a 8 hours beamline shift.

$\Delta X \sim 3 \mu\text{m}$  ,  $\Delta Z \sim 1 \mu\text{m}$






# Beam position stability (with SOFB)


on 2 straight sections during a 8 hours beamline shift.

$$\Delta X' \sim 1 \mu\text{rad} , \Delta Z' < 1 \mu\text{rad}$$




# Beam position stability (with SOFB)

on many straight sections during a 8 hours beamline shift.



# Beam position stability (?)

on many straight sections during a 6 hours ID commissioning shift.




# Transverse Bunch by Bunch Feedback (TFB) System

**Strategy adopted:** Make use of technologies and devices already developed elsewhere.

- SPring-8 digital processor chosen for its proven performance in different machines.
- BPM, RF frontend, stripline kicker developed in house

**System commissioned in Dec'06** ( ~6 months after the TFB project started)

- With a single chain, the beam stabilised up to **300 mA** (maximum authorised value) **at zero chromaticity, in both horizontal and vertical planes.**



⇒ suppress also ions related instabilities (fast and slow)  
 ⇒ almost no beam size dependence with current

**Permanently used in routine operation since April 2007**

	<b>HU640</b>	<b>HU256</b>	<b>HU80</b>	<b>U20</b>
<b>Period [mm]</b>	<b>640</b>	<b>256</b>	<b>80</b>	<b>20</b>
<b>Num. Periods</b>	<b>14</b>	<b>12</b>	<b>19</b>	<b>98</b>
<b>Type</b>	<b>Electro-magnetic</b>	<b>Electro-magnetic</b>	<b>Apple-II</b>	<b>Hybrid in-vacuum</b>
<b>Gap [mm]</b>	<b>19</b>	<b>15 (V) 50 (H)</b>	<b>15.5 - 250</b>	<b>5.5 - 30</b>
<b>Polarization</b>	<b>Elliptical</b>	<b>Elliptical</b>	<b>Elliptical</b>	<b>Linear H</b>
<b>Peak Field [T]</b>	<b>0.09 (H) 0.11 (V)</b>	<b>0.28 (H) 0.40 (V)</b>	<b>0.75 (H) 0.98 (V)</b>	<b>0.95</b>
<b>Quasi-Periodic</b>	<b>N</b>	<b>Y</b>	<b>Y</b>	<b>N</b>
<b>Photon Energy</b>	<b>5 – 40 eV</b>	<b>10 – 1000 eV</b>	<b>40 – 1600 eV</b>	<b>3 – 18 keV</b>
<b>Quantity</b>	<b>1</b>	<b>3</b>	<b>3</b>	<b>3</b>

## Insertion Devices for phase 1 beamlines


**HU640**  
**10 m**




**3 x HU80**



**3 x U20**



**2 x HU256**




---

## 14 ID's to build for Phase 2 Beamlines

- 4 In vacuum Undulators (3 U20 + 1 U24)
- 8 Apple II Undulators: HU60, HU52, HU44, HU34
- 1 In vacuum Wiggler (WSV50)
- 1 EMPHU Undulator
  
- + R&D on 1 Cryogenic Undulator

# 9 Beamlines are taking beam

## 6 from IDs and 3 from BM



Expert Users are already there.

External Users from November onwards


Commissioning of phase 2 beamlines is starting



- **Since the beginning of 2007, the main part of the operation time is dedicated to the commissioning of the beamlines**
- **In 2007, 4900 hours are scheduled:**
  - 3100 for the beamlines commissioning (and RP tests)**
  - 1800 for the commissioning of the storage ring**
- **Routine operation at 200 mA for beamlines**
  - 300mA for RP qualification of beamline hutches**
- **Machine availability is quite good : > 93% since beginning of 2007**
  - Very few RF trips : Excellent reliability of RF system**
  - The injector works well despite some recurrent failures on PS**
- **Machine operators fully trained.**
- **Assisted by ~50 part-time operators from Machine and support divisions**

# Machine operation

From January to July 2007, **93.8%** of the 1426 total hours of beam were delivered to beam lines




## **Main Objectives for 2008**

---

- ❖ **4000 hours for beamline operation + 1500 h for machine**
- ❖ **500mA operation (with 2<sup>nd</sup> cryomodule)**
- ❖ **Implement top-up injection**
- ❖ **Single bunch and 8 bunches operation**
- ❖ **Secure beam stability :**
  - Compensate further Insertion Devices effects**
  - Implement X-BPMs in front-ends**
  - Set Fast Orbit FeedBack in operation**
- ❖ **Build, measure and install new Insertion devices**
- ❖ **Install new Front-Ends for phase 2 beamlines**

# Short pulses

Preliminary results with a low alpha lattice to produce short pulses



**I wish you a fruitful meeting !**

Jean-Marc FILHOL